

TEST REPORT

Report Number Report Date Page Client Order

R633648 17-Feb-2017 1 of 1 02102017.001

Kurt O'Connor K.F. O'Connor & Associate, LLC 13574 Landser Place Carmel, IN 46033

EMAIL k.f.oconnor@sbcglobal.net

TEL 317-319-3660 **FAX NO FAX**

This document contains privileged and confidential information intended only for the client addressed. Use or dissemination by others is strictly prohibited. If not the intended recipient, please notify sender.

RECEIVED

1 Test Bar

IDENTIFICATION

Delphi K-Alloy

MATERIAL

A304

CONDITION AS RECEIVED As Cast, Die Casting

TEST PER

Client Instructions

PROPERTIES AS SUPPLIED

Differential Scanning Calorimetry

Heating Rate	20 °C/min
Solidus Temperature	566 °C
Equivalent Solidus Temperature	1051 °F
Liquidus Temperature	602°C
Equivalent Liquidus Temperature	1116°F
Disposition	For Information

Attachments

Heating chart is attached.



This document, including all Disclosures and Limitations, constitutes the entire report of all AB lacing test services and results. These tests were performed in accordance with Client and Operations Manual requirements.

Signed by Eric E. Dirats, General Manager.

